Location: 19.0.1C Date: 07-11-2025

Contract:

Filename:

grid5

SN: Revision:

Engineer: Study Case: LF

Base

Config.: Normal

### **Electrical Transient Analyzer Program**

# **Load Flow Analysis**

Loading Category (1): Design

Generation Category (1): Design

Load Diversity Factor: None

	Swing	V-Control	Load	Total
Number of Buses:	1	2	6	9

				Line/Cable/				
	XFMR2	XFMR3	Reactor	Busway	Impedance	Tie PD	Total	
Number of Branches:	5	0	0	3	0	0	8	

Method of Solution: Adaptive Newton-Raphson Method

Maximum No. of Iteration: 99

Precision of Solution: 0.0001000

System Frequency: 60.00 Hz
Unit System: English

Project Filename: grid5

 $Output \ Filename: \\ C:\Users\owner's\Desktop\PSA\ PBL\grid5\Untitled.lfr$ 

Project: ETAP Page: 2 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: Config.: grid5 Normal

# **Adjustments**

Tolerance	Apply Adjustments	Individual /Global	Percent
Transformer Impedance:	Yes	Individual	
Reactor Impedance:	Yes	Individual	
Overload Heater Resistance:	No		
Transmission Line Length:	No		
Cable / Busway Length:	No		
Temperature Correction	Apply Adjustments	Individual /Global	Degree C
Transmission Line Resistance:	Yes	Individual	
Cable / Busway Resistance:	Yes	Individual	

Location: 19.0.1C Date: 07-11-2025

Contract:

Engineer: Study Case: LF Revision: Base

Filename: grid5 Config.: Normal

## **Bus Input Data**

	91

SN:

Bus			Initial Vo	oltage	Constan	nt kVA	Constant Z		Constant I		Generic	
ID	kV	Sub-sys	% Mag.	Ang.	MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar
Bus1	11.000	1	100.0	0.0	0.272	0.169	0.068	0.042				
Bus2	129.400	1	100.0	0.0								
Bus3	129.500	1	100.0	0.0								
Bus4	129.400	1	100.0	0.0								
Bus5	10.760	1	100.0	0.0	1.360	0.843	0.325	0.202				
Bus6	10.760	1	102.2	0.0	0.068	0.042	0.016	0.010				
Bus7	129.400	1	100.0	0.0	0.007	0.004	0.002	0.001				
Bus8	10.800	1	101.9	0.0	0.586	0.343	0.115	0.071				
Bus9	0.414	1	100.0	0.0	0.041	0.025	0.008	0.005				
Total Number of Buses: 9					2.333	1.426	0.534	0.331	0.000	0.000	0.000	0.000

G	Generation Bus						Generation		Mvar Limits		
ID	kV	Туре	Sub-sys	% Mag.	Angle	MW	Mvar	% PF	Max	Min	
Bus1	11.000	Swing	1	100.0	0.0						
Bus6	10.760	Voltage Control	1	102.2	0.0	0.000			0.000	0.000	
Bus8	10.800	Voltage Control	1	101.9	0.0	0.000			37.211	0.000	
						0.000	0.000				

ETAP 4 Project: Page: 19.0.1C Location: Date: 07-11-2025 Contract: SN: Engineer: Revision: Base Study Case: LF Filename: grid5 Config.: Normal

### **Line/Cable/Busway Input Data**

#### ohms or siemens/1000 ft per Conductor (Cable) or per Phase (Line/Busway)

Line/Cable/Busway			Length	Length					
ID	Library	Size	Adj. (ft)	% Tol.	#/Phase	T (°C)	R	X	Y
Linel		477	5280.0	0.0	1	75	0.044604	0.157749	0.0000010
Line3		477	5280.0	0.0	1	75	0.044604	0.157749	0.0000010
Line7		477	5280.0	0.0	1	75	0.044604	0.157749	0.0000010

Line / Cable / Busway resistances are listed at the specified temperatures.

Project: ETAP Page: 5 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Config.: Filename: grid5 Normal

## **2-Winding Transformer Input Data**

Transformer		Rating				Z Variation			% Tap Setting		Adjusted Phase		Shift	
ID	Phase	MVA	Prim. kV	Sec. kV	% Z1	X1/R1	+ 5%	- 5%	% Tol.	Prim.	Sec.	% Z	Туре	Angle
T1	3-Phase	10.000	11.000	132.000	9.00	2.47	0	0	0	0	0	9.0000	YNd	0.000
T3	3-Phase	100.000	11.000	132.000	9.00	2.47	0	0	0	0	0	9.0000	YNd	0.000
T7	3-Phase	15.000	11.000	132.000	9.00	2.47	0	0	0	0	0	9.0000	YNd	0.000
T10	3-Phase	0.500	11.000	0.415	5.20	5.10	0	0	0	0	0	5.2000	Dyn	0.000
T12	3-Phase	0.400	11.000	132.000	9.00	2.47	0	0	0	0	0	9.0000	YNd	0.000

Location: 19.0.1C Date: 07-11-2025

SN:

Contract:

Engineer: Study Case: LF Revision: Base

Filename: grid5 Config.: Normal

## **Branch Connections**

CKT/Bran	ch	Con	nnected Bus ID	% Impe	% Impedance, Pos. Seq., 100 MVA Base						
ID	Туре	From Bus	To Bus	R	Х	Z	Y				
T1	2W XFMR	Busl	Bus2	33.77	83.42	90.00					
T3	2W XFMR	Bus5	Bus4	3.38	8.34	9.00					
T7	2W XFMR	Bus8	Bus3	22.52	55.61	60.00					
T10	2W XFMR	Bus8	Bus9	200.11	1020.57	1040.00					
T12	2W XFMR	Bus6	Bus7	844.36	2085.56	2250.00					
Line1	Line	Bus3	Bus2	0.14	0.48	0.50	0.0895860				
Line3	Line	Bus3	Bus4	0.14	0.48	0.50	0.0895860				
Line7	Line	Bus5	Bus6	19.46	68.84	71.53	0.0006221				

Location: 19.0.1C Date: 07-11-2025

SN:

Contract:

Engineer: Study Case: LF Revision: Base

Filename: grid5 Config.: Normal

# LOAD FLOW REPORT

	Bus		Volt	age	Gener	ation	Lo	ad			Load Flow				XFMR
	ID	kV	% Mag.	Ang.	MW	Mvar	MW	Mvar		ID	MW	Mvar	Amp	%PF	%Тар
* Bus1		11.000	100.000	0.0	2.912	-0.119	0.340	0.211	Bus2		2.572	-0.330	136.1	-99.2	
Bus2		129.400	101.430	-1.3	0.000	0.000	0.000	0.000	Bus3		2.549	-0.386	11.3	-98.9	
									Bus1		-2.549	0.386	11.3	-98.9	
Bus3		129.500	101.350	-1.3	0.000	0.000	0.000	0.000	Bus2		-2.549	0.298	11.3	-99.3	
									Bus4		1.790	1.023	9.1	86.8	
									Bus8		0.759	-1.321	6.7	-49.8	
Bus4		129.400	101.421	-1.3	0.000	0.000	0.000	0.000	Bus3		-1.790	-1.111	9.3	85.0	
									Bus5		1.790	1.111	9.3	85.0	
Bus5		10.760	101.483	-1.4	0.000	0.000	1.695	1.050	Bus6		0.093	0.057	5.8	85.2	
									Bus4		-1.788	-1.108	111.2	85.0	
Bus6		10.760	101.424	-1.4	0.000	0.000	0.085	0.053	Bus5		-0.093	-0.058	5.8	85.0	
									Bus7		0.008	0.005	0.5	84.9	
Bus7		129.400	101.018	-1.5	0.000	0.000	0.008	0.005	Bus6		-0.008	-0.005	0.0	85.0	
* Bus8		10.800	101.852	-1.7	0.000	1.782	0.705	0.417	Bus3		-0.754	1.334	80.4	-49.2	
									Bus9		0.049	0.031	3.0	84.8	
Bus9		0.414	99.829	-2.0	0.000	0.000	0.049	0.030	Bus8		-0.049	-0.030	80.8	85.1	

<sup>\*</sup> Indicates a voltage regulated bus (voltage controlled or swing type machine connected to it)

<sup>#</sup> Indicates a bus with a load mismatch of more than 0.1 MVA

19.0.1C Location: Date: 07-11-2025

Contract:

Engineer: Revision: Base Study Case: LF

Filename: Config.: grid5 Normal

### **Bus Loading Summary Report**

#### **Directly Connected Load**

#### **Total Bus Load**

SN:

	Bus			Constar	nt kVA	Const	ant Z	Con	stant I	Ge	neric				Percent
	ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar	MVA	% PF	Amp	Loading
Bus1		11.000		0.272	0.169	0.068	0.042					2.931	99.4	153.8	
Bus2		129.400										2.578	98.9	11.3	
Bus3		129.500										2.871	88.8	12.6	
Bus4		129.400										2.107	85.0	9.3	
Bus5		10.760		1.360	0.843	0.335	0.208					2.104	85.0	111.2	
Bus6		10.760		0.068	0.042	0.017	0.010					0.110	85.0	5.8	
Bus7		129.400		0.007	0.004	0.002	0.001					0.010	85.0	-	
Bus8		10.800		0.586	0.343	0.119	0.074					1.935	39.0	101.6	
Bus9		0.414		0.041	0.025	0.008	0.005					0.058	85.1	80.8	

<sup>\*</sup> Indicates operating load of a bus exceeds the bus critical limit (100.0% of the Continuous Ampere rating). # Indicates operating load of a bus exceeds the bus marginal limit (95.0% of the Continuous Ampere rating).

Project: ETAP Page: 9 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: grid5 Config.: Normal

## **Branch Loading Summary Report**

CKT / Branch			D	/C-bl- @ D	_4	Transformer						
	CK1 / Br	ancn		/ Cable & Rea	ctor	6 199	Loading (	input)	Loading (	output)		
	ID	Туре	Ampacity (Amp)	Loading Amp	%	Capability (MVA)	MVA	%	MVA	%		
T1		Transformer				10.000	2.593	25.9	2.578	25.8		
Т3		Transformer				100.000	2.107	2.1	2.104	2.1		
T7		Transformer				15.000	1.532	10.2	1.524	10.2		
T10		Transformer				0.500	0.058	11.6	0.058	11.6		
T12		Transformer				0.400	0.010	2.5	0.010	2.5		

<sup>\*</sup> Indicates a branch with operating load exceeding the branch capability.

Project:		ETAP	Page:	10
Location:		19.0.1C	Date:	07-11-2025
Contract:			SN:	
Engineer:		Study Case: LF	Revision:	Base
Filename:	grid5	, <u>-</u> -	Config.:	Normal

## **Branch Losses Summary Report**

	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop
Branch ID	MW	Mvar	MW	Mvar	kW	kvar	From	То	in Vmag
Line1	2.549	-0.386	-2.549	0.298	0.1	-88.3	101.4	101.4	0.00
Line3	1.790	1.023	-1.790	-1.111	0.1	-88.4	101.4	101.4	0.01
Line7	0.093	0.057	-0.093	-0.058	0.0	-0.5	101.5	101.4	0.06
T1	2.572	-0.330	-2.549	0.386	22.7	56.1	100.0	101.4	0.57
T10	0.049	0.031	-0.049	-0.030	0.1	0.3	101.9	99.8	0.42
T12	0.008	0.005	-0.008	-0.005	0.0	0.0	101.4	101.0	0.19
T3	1.790	1.111	-1.788	-1.108	1.5	3.7	101.4	101.5	0.16
T7	0.759	-1.321	-0.754	1.334	5.3	13.1	101.4	101.9	0.58
					29.8	-103.9			

<sup>\*</sup> This Transmission Line includes Series Capacitor.

Project: ETAP Page: 11 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Config.: Filename: grid5 Normal

## **Alert Summary Report**

## % Alert Settings

	Critical	Marginal
<b>Loading</b>		
Bus	100.0	95.0
Cable / Busway	100.0	95.0
Reactor	100.0	95.0
Line	100.0	95.0
Transformer	100.0	95.0
Panel	100.0	95.0
Protective Device	100.0	95.0
Generator	100.0	95.0
Inverter/Charger	100.0	95.0
Bus Voltage		
OverVoltage	105.0	102.0
UnderVoltage	95.0	98.0
<b>Generator Excitation</b>		
OverExcited (Q Max.)	100.0	95.0
UnderExcited (Q Min.)	100.0	

## **Critical Report**

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Gen1	Generator	Under Excited	0.000	Mvar	-0.119	0.0	3-Phase
Gen2	Generator	Under Excited	0.000	Mvar	0.000	0.0	3-Phase
Gen2	Generator	Under Power	0.000	MW	0.000	0.0	3-Phase
Gen3	Generator	Under Power	0.000	MW	0.000	0.0	3-Phase

Project: ETAP Page: 12 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: Config.: grid5 Normal

# SUMMARY OF TOTAL GENERATION, LOADING & DEMAND

	MW	Mvar	MVA	% PF
Source (Swing Buses):	2.912	-0.119	2.914	99.92 Leading
Source (Non-Swing Buses):	0.000	1.782	1.782	0.00 Lagging
Total Demand:	2.912	1.663	3.353	86.84 Lagging
Total Motor Load:	2.333	1.426	2.735	85.32 Lagging
Total Static Load:	0.549	0.340	0.646	85.00 Lagging
Total Constant I Load:	0.000	0.000	0.000	
Total Generic Load:	0.000	0.000	0.000	
Apparent Losses:	0.030	-0.104		
System Mismatch:	0.000	0.000		

Number of Iterations: 2