Location: 19.0.1C Date: 07-11-2025

Contract:

SN:

Engineer: Study Case: LF Revision: Base

Filename: grid4 Config.: Normal

Electrical Transient Analyzer Program

Load Flow Analysis

Loading Category (1): Design

Generation Category (1): Design

Load Diversity Factor: None

	Swing	V-Control	Load	Total
Number of Buses:	1	1	7	9

Method of Solution: Adaptive Newton-Raphson Method

Maximum No. of Iteration: 99

Precision of Solution: 0.0001000

System Frequency: 60.00 Hz
Unit System: English

Project Filename: grid4

 Project: ETAP Page: 2 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: Config.: grid4 Normal

Adjustments

Tolerance	Apply Adjustments	Individual /Global	Percent
Transformer Impedance:	Yes	Individual	
Reactor Impedance:	Yes	Individual	
Overload Heater Resistance:	No		
Transmission Line Length:	No		
Cable / Busway Length:	No		
Temperature Correction	Apply Adjustments	Individual /Global	Degree C
Transmission Line Resistance:	Yes	Individual	
Cable / Busway Resistance:	Yes	Individual	

Location: 19.0.1C Date: 07-11-2025

SN:

Contract:

Engineer: Study Case: LF Revision: Base

Filename: grid4 Config.: Normal

Bus Input Data

						Load									
Bus			Initial Voltage		Constar	nt kVA	Constant Z		Constant I		Generic				
ID	kV	Sub-sys	% Mag.	Ang.	MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar			
Bus_1	11.000	1	100.0	0.0											
Bus_2	11.000	1	100.0	0.0											
Bus_3	211.000	1	100.0	0.0											
Bus_4	211.000	1	100.0	0.0	26.907	29.598	5.661	6.227							
Bus_5	211.000	1	100.0	0.0	17.000	10.536	3.577	2.217							
Bus_6	211.000	1	100.0	0.0	14.400	19.200	3.030	4.040							
Bus_7	211.000	1	100.0	0.0	20.400	12.643	4.292	2.660							
Bus_8	211.000	1	100.0	0.0											
Bus_9	9.500	1	100.0	0.0	13.600	8.429	3.400	2.107							
Total Number of Buses: 9					92.307	80.405	19.960	17.251	0.000	0.000	0.000	0.000			

G	Generation Bus						Generation	Mvar Limits		
ID	kV	Туре	Sub-sys	% Mag.	Angle	MW	Mvar	% PF	Max	Min
Bus_1	11.000	Swing	1	100.0	0.0					
Bus_2	11.000	Voltage Control	1	100.0	0.0	40.000			84.678	0.000
Bus_9	9.500	Mvar/PF Control	1	100.0	0.0	85.000	-52.678	-85.0		
						125.000	-52.678			

ETAP 4 Project: Page: 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: grid4 Config.: Normal

Line/Cable/Busway Input Data

ohms or siemens/1000 ft per Conductor (Cable) or per Phase (Line/Busway)

Line/Cable/Busway		Length							
ID	Library	Size	Adj. (ft)	% Tol.	#/Phase	T (°C)	R	X	Y
Linel		477	5280.0	0.0	1	100	0.048250	0.157749	0.0000010
Line3		477	5280.0	0.0	1	100	0.048250	0.157749	0.0000010
Line5		477	5280.0	0.0	1	100	0.048250	0.157749	0.0000010
Line7		477	5280.0	0.0	1	100	0.048250	0.157749	0.0000010
Line9		477	5280.0	0.0	1	100	0.048250	0.157749	0.0000010
Line10		477	5280.0	0.0	1	100	0.048250	0.157749	0.0000010

Line / Cable / Busway resistances are listed at the specified temperatures.

Project: ETAP Page: 5 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Config.: Filename: grid4 Normal

2-Winding Transformer Input Data

	Transformer				Rating				Z Variation	1	% Tap	Setting	Adjusted	Phase	Shift
	ID	Phase	MVA	Prim. kV	Sec. kV	% Z1	X1/R1	+ 5%	- 5%	% Tol.	Prim.	Sec.	% Z	Type	Angle
T1		3-Phase	157.000	11.000	230.000	10.00	34.10	0	0	0	0	0	10.0000	YNd	0.000
T3		3-Phase	100.000	11.000	230.000	10.00	34.10	0	0	0	0	0	10.0000	YNd	0.000
T4		3-Phase	100.300	230.000	11.000	10.00	34.10	0	0	0	0	0	10.0000	Dyn	0.000

Project: ETAP Page: 6 19.0.1C Location: Date: 07-11-2025

Contract:

Engineer: Revision: Base Study Case: LF Filename:

Config.: grid4 Normal

Branch Connections

SN:

CKT	/Branch	Co.	nnected Bus ID	% Impe	% Impedance, Pos. Seq., 100 MVA Base					
ID	Туре	From Bus	To Bus	R	X	Z	Y			
T1	2W XFMR	Bus_1	Bus_3	0.19	6.37	6.37				
T3	2W XFMR	Bus_2	Bus_3	0.29	10.00	10.00				
T4	2W XFMR	Bus_8	Bus_9	0.29	9.97	9.97				
Line1	Line	Bus_3	Bus_4	0.05	0.16	0.16	0.2719868			
Line3	Line	Bus_4	Bus_5	0.05	0.16	0.16	0.2719868			
Line5	Line	Bus_6	Bus_3	0.05	0.16	0.16	0.2719868			
Line7	Line	Bus_7	Bus_5	0.05	0.16	0.16	0.2719868			
Line9	Line	Bus_8	Bus_6	0.05	0.16	0.16	0.2719868			
Line10	Line	Bus_8	Bus_7	0.05	0.16	0.16	0.2719868			

Location: 19.0.1C Date: 07-11-2025

SN:

Contract:

Engineer: Study Case: LF
Filename: grid4
Revision: Base
Config.: Normal

LOAD FLOW REPORT

Bus		Volt	age	Gener	ation	Lo	ad			Load Flow				XFMR
ID	kV	% Mag.	Ang.	MW	Mvar	MW	Mvar		ID	MW	Mvar	Amp	%PF	%Tap
* Bus_1	11.000	100.000	0.0	-11.468	107.376	0.000	0.000	Bus_3		-11.468	107.376	5667.8	-10.6	
* Bus_2	11.000	100.000	2.9	40.000	67.734	0.000	0.000	Bus_3		40.000	67.734	4128.7	50.8	
Bus_3	211.000	101.581	0.6	0.000	0.000	0.000	0.000	Bus_4		33.892	74.581	220.7	41.4	
								Bus_6		-5.759	86.919	234.6	-6.6	
								Bus_1		11.686	-99.952	271.1	-11.6	
								Bus_2		-39.819	-61.549	197.5	54.3	
Bus_4	211.000	101.425	0.6	0.000	0.000	32.731	36.004	Bus_3		-33.854	-74.695	221.2	41.3	
								Bus_5		1.124	38.691	104.4	2.9	
Bus_5	211.000	101.352	0.6	0.000	0.000	20.674	12.813	Bus_4		-1.115	-38.899	105.1	2.9	
								Bus_7		-19.559	26.086	88.0	-60.0	
Bus_6	211.000	101.424	0.6	0.000	0.000	17.517	23.356	Bus_3		5.801	-87.017	235.3	-6.7	
								Bus_8		-23.318	63.662	182.9	-34.4	
Bus_7	211.000	101.315	0.6	0.000	0.000	24.806	15.373	Bus_5		19.565	-26.302	88.5	-59.7	
								Bus_8		-44.371	10.929	123.4	-97.1	
Bus_8	211.000	101.320	0.7	0.000	0.000	0.000	0.000	Bus_6		23.344	-63.813	183.5	-34.4	
								Bus_7		44.382	-11.126	123.6	-97.0	
								Bus_9		-67.726	74.939	272.8	-67.1	
Bus_9	9.500	98.951	5.7	85.000	-52.678	16.929	10.492	Bus_8		68.071	-63.170	5703.6	-73.3	

^{*} Indicates a voltage regulated bus (voltage controlled or swing type machine connected to it)

[#] Indicates a bus with a load mismatch of more than 0.1 MVA

19.0.1C Location: Date: 07-11-2025

SN:

Engineer: Revision: Base Study Case: LF

Filename: Config.: grid4 Normal

Bus Loading Summary Report

Directly Connected Load Total Bus Load

	Bus			Constant kVA		Constant Z		Constant I		Generic					Percent
	ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar	MVA	% PF	Amp	Loading
Bus_1		11.000										107.987	10.6	5667.8	
Bus_2		11.000										78.663	50.8	4128.7	
Bus_3		211.000										167.809	27.2	452.0	
Bus_4		211.000		26.907	29.598	5.824	6.406					82.009	41.3	221.2	
Bus_5		211.000		17.000	10.536	3.674	2.277					44.052	46.9	118.9	
Bus_6		211.000		14.400	19.200	3.117	4.156					90.087	25.9	243.0	
Bus_7		211.000		20.400	12.643	4.406	2.730					51.581	86.0	139.3	
Bus_8		211.000										101.008	67.1	272.8	
Bus_9		9.500		13.600	8.429	3.329	2.063					105.903	80.3	6504.4	

Contract:

^{*} Indicates operating load of a bus exceeds the bus critical limit (100.0% of the Continuous Ampere rating). # Indicates operating load of a bus exceeds the bus marginal limit (95.0% of the Continuous Ampere rating).

Project: ETAP Page: 9 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Config.: Filename: grid4 Normal

Branch Loading Summary Report

	CKT / Branch			/C 11 . 0 D		Transformer						
	CK1 / Branch		Busway / Cable & Reactor			Capability	Loading ((input)	Loading (output)			
	ID	Туре	Ampacity (Amp)	Loading Amp	%	(MVA)	MVA	%	MVA	%		
T1		Transformer				157.000	107.987	68.8	100.633	64.1		
T3		Transformer				100.000	78.663	78.7	73.306	73.3		
T4		Transformer				100.300	101.008	100.7	92.866	92.6		

^{*} Indicates a branch with operating load exceeding the branch capability.

Project:		ETA	AP	Page:	10
Location:		19.0.	.1C	Date:	07-11-2025
Contract:				SN:	
Engineer:		Study Cas	ise: I.F	Revision:	Base
Filename:	grid4	State, State		Config.:	Normal

Branch Losses Summary Report

	From-To Bus		To-From	Bus Flow	Los	ses	% Bus '	Vd % Drop	
Branch ID	MW	Mvar	MW	Mvar	kW	kvar	From	То	in Vmag
Line1	33.892	74.581	-33.854	-74.695	37.3	-113.8	101.6	101.4	0.16
Line10	-44.371	10.929	44.382	-11.126	11.7	-196.9	101.3	101.3	0.00
Line3	1.124	38.691	-1.115	-38.899	8.4	-207.9	101.4	101.4	0.07
Line5	-5.759	86.919	5.801	-87.017	42.2	-97.9	101.6	101.4	0.16
Line7	-19.559	26.086	19.565	-26.302	6.0	-215.6	101.4	101.3	0.04
Line9	-23.318	63.662	23.344	-63.813	25.7	-151.4	101.4	101.3	0.10
T1	-11.468	107.376	11.686	-99.952	217.7	7424.3	100.0	101.6	6.81
T3	40.000	67.734	-39.819	-61.549	181.4	6185.2	100.0	101.6	6.81
T4	-67.726	74.939	68.071	-63.170	345.1	11768.6	101.3	99.0	8.17
					875.4	24394.6			

^{*} This Transmission Line includes Series Capacitor.

Project: ETAP Page: 11 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Config.: Filename: grid4 Normal

Alert Summary Report

% Alert Settings

	Critical	Marginal
Loading		
Bus	100.0	95.0
Cable / Busway	100.0	95.0
Reactor	100.0	95.0
Line	100.0	95.0
Transformer	100.0	95.0
Panel	100.0	95.0
Protective Device	100.0	95.0
Generator	100.0	95.0
Inverter/Charger	100.0	95.0
Bus Voltage		
OverVoltage	105.0	102.0
UnderVoltage	95.0	98.0
Generator Excitation		
OverExcited (Q Max.)	100.0	95.0
UnderExcited (Q Min.)	100.0	

Critical Report

Device ID	Type	Type Condition		Unit	Operating	% Operating	Phase Type
Gen1	Generator	Over Excited	69.871	Mvar	107.376	153.7	3-Phase
Gen1	Generator	Under Power	0.000	MW	-11.468	0.0	3-Phase
Wind Farm	Wind Turbine Generator	Overload	85.000	MW	85.000	100.0	3-Phase

Project: ETAP Page: 12 19.0.1C Location: Date: 07-11-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: Config.: grid4 Normal

SUMMARY OF TOTAL GENERATION, LOADING & DEMAND

	MW	Mvar	MVA	% PF
Source (Swing Buses):	-11.468	107.376	107.987	10.62 Leading
Source (Non-Swing Buses):	125.000	15.056	125.903	99.28 Lagging
Total Demand:	113.532	122.432	166.970	68.00 Lagging
Total Motor Load:	92.307	80.405	122.415	75.40 Lagging
Total Static Load:	20.350	17.632	26.926	75.58 Lagging
Total Constant I Load:	0.000	0.000	0.000	
Total Generic Load:	0.000	0.000	0.000	
Apparent Losses:	0.875	24.395		
System Mismatch:	0.000	0.000		

Number of Iterations: 4

Location: 19.0.1C Date: 07-11-2025

Contract: Engineer:

Filename:

grid4

Study Case: SM

SN:

Revision: Base

Config.: Normal

Electrical Transient Analyzer Program

Short-Circuit Analysis

ANSI Standard

3-Phase, LG, LL, & LLG Fault Currents

1/2 Cycle Network

	Swing	V-Control	Load	Total			
Number of Buses:	1	1	7	9			
Number of Branches:	XFMR2	XFMR3	Reactor	Line/Cable/ Busway 6	Impedance 0	Tie PD 0	Total 9
Number of Machines:	Synchronous Generator 2	Power Grid	Synchronous Motor 0	Induction Machines 0	Lumped Load 5		

System Frequency: 60.00
Unit System: English

Project Filename: grid4

Output Filename: C:\Users\owner's\Desktop\PSA PBL\grid4\grid4\Untitled.SQ1S

2 Project: ETAP Page: 19.0.1C 07-11-2025 Location: Date: Contract: SN: Engineer: Revision: Base Study Case: SM Filename: Config.: grid4 Normal

Adjustments

Tolerance	Apply Adjustments	Individual /Global	Percent
Transformer Impedance:	Yes	Individual	
Reactor Impedance:	Yes	Individual	
Overload Heater Resistance:	No		
Transmission Line Length:	No		
Cable / Busway Length:	No		
Temperature Correction	Apply Adjustments	Individual /Global	Degree C
Transmission Line Resistance:	Yes	Individual	
Cable / Busway Resistance:	Yes	Individual	

3 Project: **ETAP** Page: 19.0.1C 07-11-2025 Date: Location: Contract: SN: Engineer: Revision: Base Study Case: SM Filename: grid4 Config.: Normal

Bus Input Data

	Initial Voltage					
ID	Туре	Nom. kV	Base kV	Sub-sys	%Mag.	Ang.
Bus_1	SWNG	11.000	11.000	1	100.00	0.00
Bus_2	Gen.	11.000	11.000	1	100.00	0.00
Bus_3	Load	211.000	230.000	1	100.00	30.00
Bus_4	Load	211.000	230.000	1	100.00	30.00
Bus_5	Load	211.000	230.000	1	100.00	30.00
Bus_6	Load	211.000	230.000	1	100.00	30.00
Bus_7	Load	211.000	230.000	1	100.00	30.00
Bus_8	Load	211.000	230.000	1	100.00	30.00
Bus 9	Load	9.500	11.000	1	100.00	0.00

9 Buses Total

All voltages reported by ETAP are in % of bus Nominal kV. Base kV values of buses are calculated and used internally by ETAP .

 Project:
 ETAP
 Page:
 4

 Location:
 19.0.1C
 Date:
 07-11-2025

Contract: SN:

Engineer: Study Case: SM Revision: Base
Filename: grid4 Config.: Normal

Line/Cable/Busway Input Data

ohms or siemens per 1000 ft per Conductor (Cable) or per Phase (Line/Busway)

Line/Cable/Busway			Leng	th								
ID	Library	Size	Adj. (ft)	% Tol.	#/Phase	T (°C)	R1	X1	Y1	R0	X0	Y0
Line1		477	5280.0	0.0	1	-30	0.029292	0.1577493	0.000001	0.0803398	0.4853866	0.0000005
Line3		477	5280.0	0.0	1	-30	0.029292	0.1577493	0.000001	0.0803398	0.4853866	0.0000005
Line5		477	5280.0	0.0	1	-30	0.029292	0.1577493	0.000001	0.0803398	0.4853866	0.0000005
Line7		477	5280.0	0.0	1	-30	0.029292	0.1577493	0.000001	0.0803398	0.4853866	0.0000005
Line9		477	5280.0	0.0	1	-30	0.029292	0.1577493	0.000001	0.0803398	0.4853866	0.0000005
Line10		477	5280.0	0.0	1	-30	0.029292	0.1577493	0.000001	0.0803398	0.4853866	0.0000005

Line / Cable / Busway resistances are listed at the specified temperatures.

Location: 19.0.1C Date: 07-11-2025

Contract: SN:

Engineer: Study Case: SM Revision: Base

Filename: grid4 Config.: Normal

2-Winding Transformer Input Data

	Transformer	Rating						Z Variatio	n	% Tap	Setting	Adjusted	Phase Shift	
	ID	MVA	Prim. kV	Sec. kV	% Z	X/R	+ 5%	- 5%	% Tol.	Prim.	Sec.	% Z	Type	Angle
T1		157.000	11.000	230.000	10.00	34.10	0	0	0	0	0	10.00	YNd	30.00
Т3		100.000	11.000	230.000	10.00	34.10	0	0	0	0	0	10.00	YNd	30.00
T4		100.300	230.000	11.000	10.00	34.10	0	0	0	0	0	10.00	Dyn	30.00

2-Winding Transformer Grounding Input Data

Grounding

	Transformer		Rating		Conn.		Primary				Secondary		
	ID	MVA	Prim. kV	Sec. kV	Type	Туре	kV	Amp	ohm	Туре	kV	Amp	ohm
T	1	157.000	11.000	230.000	D/Y					Solid			
T	3	100.000	11.000	230.000	D/Y					Solid			
T	4	100.300	230.000	11.000	D/Y					Solid			

Location: 19.0.1C Date: 07-11-2025

Contract: SN:

Engineer: Study Case: SM Revision: Base
Filename: grid4 Config.: Normal

Branch Connections

CKT/Bra	nch	Cor	nnected Bus ID	% Impedance, Pos. Seq., 100 MVAb						
ID	Type	From Bus	To Bus	R	X	Z	Y			
T1	2W XFMR	Bus_1	Bus_3	0.19	6.37	6.37				
T3	2W XFMR	Bus_2	Bus_3	0.29	10.00	10.00				
T4	2W XFMR	Bus_8	Bus_9	0.29	9.97	9.97				
Line1	Line	Bus_3	Bus_4	0.03	0.16	0.16	0.2719868			
Line3	Line	Bus_4	Bus_5	0.03	0.16	0.16	0.2719868			
Line5	Line	Bus_6	Bus_3	0.03	0.16	0.16	0.2719868			
Line7	Line	Bus_7	Bus_5	0.03	0.16	0.16	0.2719868			
Line9	Line	Bus_8	Bus_6	0.03	0.16	0.16	0.2719868			
Line10	Line	Bus_8	Bus_7	0.03	0.16	0.16	0.2719868			

 Project:
 ETAP
 Page:
 7

 Location:
 19.0.1C
 Date:
 07-11-2025

Contract: SN:

Engineer: Study Case: SM Revision: Base

Filename: grid4 Config.: Normal

Synchronous Generator Input Data

Positive Seq. Impedance

Synchronous Genera			% Xd"					Grounding		Zero Seq. Impedance					
ID	Туре	MVA	kV	RPM	X"/R	% R	Adj.	Tol.	% Xd'	Conn.	Туре	Amp	X/R	% R0	% X0
Gen1	Steam Turbo	100.000	11.000	1800	19.00	1.000	19.00	0.0	28.00	Wye	Solid		7.00	1.000	7.00
Gen3	Steam Turbo	111.765	11.000	1800	19.00	1.000	19.00	0.0	28.00	Wye	Solid		7.00	1.000	7.00

Total Connected Synchronous Generators (= 2): 211.765 MVA

Location: 19.0.1C Date: 07-11-2025

Contract: SN:

Engineer: Study Case: SM Revision: Base

Filename: grid4 Config.: Normal

Lumped Load Input Data

Lumped Load Motor Loads

					Impedance									
Lumped Load	Ra	ting	<u>%</u>	Load	Loa	ading X/R Ratio		Ratio	(M	achine Bas	se)		Groundin	g
ID	kVA	kV	MTR	STAT	kW	kvar	X"/R	X'/R	% R	% X"	% X'	Conn.	Type	Amp.
Data Center	25000.0	230.000	80	20	17000.0	10535.7	10.00	10.00	1.538	15.38	23.08	Delta		
Manufacturing Plant	50000.0	230.000	80	20	26906.9	29597.6	10.00	10.00	1.538	15.38	23.08	Delta		
Resident_Commercial_z	20000.0	9.500	80	20	13600.0	8428.5	10.00	10.00	1.538	15.38	23.08	Delta		
one Shopping Mall	30000.0	230.000	80	20	20400.0	12642.8	10.00	10.00	1.538	15.38	23.08	Delta		
University	30000.0	230.000	80	20	14400.0	19200.0	10.00	10.00	1.538	15.38	23.08	Delta		

Total Connected Lumped Loads (= 5): 155000.0 kVA

Location: 19.0.1C Date: 07-11-2025

Contract: SN:

Engineer: Study Case: SM Revision: Base
Filename: grid4 Config.: Normal

SHORT- CIRCUIT REPORT

Fault at bus: Bus_4

 $Prefault\ voltage\ =\ 211.000\ kV \\ =\ 100.00\ \%\ of\ nominal\ bus\ kV\ (\ 211.000\ kV)$

= 91.74 % of base kV (230.000 kV)

Contribution		3-Phase Fault			Line-T	To-Ground	Fault	Positive & Zero Sequence Impedances Looking into "From Bus"				
From Bus	To Bus	% V	kA	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
ID	ID	From Bus	Symm. rms	Va			Ia	310	R1	X1	R0	X0
Bus_4	Total	0.00	4.315	0.00	97.49	95.36	4.638	4.638	3.48E-001	5.33E+000	1.81E-001	4.29E+000
Bus_3	Bus_4	1.63	2.338	3.92	96.72	94.23	2.970	3.865	5.41E-001	9.83E+000	2.17E-001	5.15E+000
Bus_5	Bus_4	0.96	1.382	1.24	97.41	95.26	1.244	0.773	1.13E+000	1.66E+001	1.09E+000	2.58E+001
Manufacturing Plant	Bus_4	91.74	0.596	91.74	91.74	91.74	0.424	0.000	3.85E+000	3.85E+001		
Bus_6	Bus_3	2.05	0.608	3.67	96.95	94.60	0.171	0.773	2.76E+000	3.72E+001	6.84E-001	2.33E+001
Bus_1	Bus_3	24.12	0.892	58.46	60.23	91.10	1.591	2.833 *	1.19E+000	2.54E+001	1.87E-001	6.37E+000
Bus_2	Bus_3	34.88	0.838	62.92	64.76	91.08	1.208	1.805 *	1.19E+000	2.70E+001	2.93E-001	1.00E+001
Bus_7	Bus_5	1.72	1.087	2.33	97.30	95.12	1.035	0.773	1.21E+000	2.10E+001	1.01E+000	2.53E+001
Data Center	Bus_5	91.74	0.295	91.74	91.74	91.74	0.210	0.000	7.69E+000	7.69E+001		
Bus_8	Bus_6	2.23	0.258	3.24	97.16	94.93	0.078	0.773	3.33E+000	8.74E+001	7.65E-001	2.38E+001
University	Bus_6	91.74	0.350	91.74	91.74	91.74	0.249	0.000	6.41E+000	6.41E+001		
Gen1	Bus_1	91.74	18.655	91.74	91.74	91.74	11.620	0.000	1.00E+000	1.90E+001	1.00E+000	7.00E+000
Gen3	Bus_2	91.74	17.532	91.74	91.74	91.74	10.912	0.000	8.95E-001	1.70E+001	8.95E-001	6.26E+000
Bus_8	Bus_7	2.23	0.736	3.24	97.16	94.93	0.785	0.773	1.11E+000	3.07E+001	9.25E-001	2.48E+001
Shopping Mall	Bus_7	91.74	0.351	91.74	91.74	91.74	0.250	0.000	6.41E+000	6.41E+001		

[#] Indicates fault current contribution is from three-winding transformers

^{*} Indicates a zero sequence fault current contribution (310) from a grounded Delta-Y transformer

Project: **ETAP** Page: 10 19.0.1C 07-11-2025 Location: Date: Contract: SN: Engineer: Revision: Base Study Case: SM Filename: grid4 Config.: Normal

Short-Circuit Summary Report

1/2 Cycle - 3-Phase, LG, LL, & LLG Fault Currents

Prefault Voltage = 100 % of the Bus Nominal Voltage

Bus		3-Phase Fault		Line-to-Ground Fault			Line-to-Line Fault			*Line-to-Line-to-Ground			
ID	kV	Real	Imag.	Mag.	Real	Imag.	Mag.	Real	Imag.	Mag.	Real	Imag.	Mag.
Bus_4	211.000	0.281	-4.306	4.315	0.297	-4.629	4.638	3.753	0.274	3.763	3.630	2.730	4.542

All fault currents are symmetrical (1/2 Cycle network) values in rms kA. * LLG fault current is the larger of the two faulted line currents.

Project: ETAP Page: 11 19.0.1C 07-11-2025 Date: Location: Contract: SN: Engineer: Revision: Base Study Case: SM Filename: grid4 Config.: Normal

Sequence Impedance Summary Report

Bus		Positive Seq. Imp. (ohm)			Negative Seq. Imp. (ohm)			Zero Seq. Imp. (ohm)			Fault Zf (ohm)		
ID	kV	Resistance	Reactance	Impedance	Resistance	Reactance	Impedance	Resistance	Reactance	Impedance	Resistance	Reactance	Impedance
Rus 4	211 000	1.83912	28 16960	28 22957	2 24758	27.75169	27.84255	0.95686	22 71052	22 73066	0.00000	0.00000	0.00000

Project: ETAP Page: 12 19.0.1C 07-11-2025 Location: Date: Contract: SN: Engineer: Revision: Base Study Case: SM Filename: Config.: grid4 Normal

Sequence-of-Operation Event Summary Report

Symmetrical 3-Phase Fault at Bus_4.

Time (ms)	ID	If (kA)	T1 (ms)	T2 (ms)	Condition
99.4	Relayl	1.382	99.4		Phase - OC1 - 51
105	Relay2	0.994	105		Phase - OC1 - 51
133	CB_7		33.3		Tripped by Relay1 Phase - OC1 - 51
133	CB_8		33.3		Tripped by Relay1 Phase - OC1 - 51
139	CB_17		33.3		Tripped by Relay2 Phase - OC1 - 51
139	CB_18		33.3		Tripped by Relay2 Phase - OC1 - 51