Location: 19.0.1C Date: 06-25-2025

Contract:

SN:

Config.:

Engineer:

Study Case: LF

Revision: Base

Normal

Filename: grid2

Electrical Transient Analyzer Program

Load Flow Analysis

Loading Category (1): Design

Generation Category (1): Design

Load Diversity Factor: None

	Swing	V-Control	Load	Total
Number of Buses:	1	2	6	9

				Line/Cable/			
	XFMR2	XFMR3	Reactor	Busway	Impedance	Tie PD	Total
Number of Branches:	3	0	0	6	0	0	9

Method of Solution: Adaptive Newton-Raphson Method

Maximum No. of Iteration: 99

Precision of Solution: 0.0001000

System Frequency: 60.00 Hz
Unit System: English

Project Filename: grid2

 $Output \ Filename: \\ C:\Users\owner's\Desktop\PSA\ PBL\grid2\Grid2\Untitled.lfr$

Project: ETAP Page: 2 19.0.1C Location: Date: 06-25-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: Config.: grid2 Normal

Adjustments

Tolerance	Apply Adjustments	Individual /Global	Percent
Transformer Impedance:	Yes	Individual	
Reactor Impedance:	Yes	Individual	
Overload Heater Resistance:	No		
Transmission Line Length:	No		
Cable / Busway Length:	No		
Temperature Correction	Apply Adjustments	Individual /Global	Degree C
Transmission Line Resistance:	Yes	Individual	
Cable / Busway Resistance:	Yes	Individual	

Location: 19.0.1C Date: 06-25-2025

Contract:

Engineer:

Filename:

grid2

SN:

Study Case: LF Revision: Base

Config.: Normal

Bus Input Data

					Load							
Bus			Initial Vo	oltage	Constar	nt kVA	Const	ant Z	Cons	tant I	Gen	eric
ID	kV	Sub-sys	% Mag.	Ang.	MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar
Busl	11.300	1	100.0	0.0								
Bus2	20.000	1	100.0	0.0								
Bus3	20.000	1	105.0	0.0	6.800	4.214	1.752	1.086				
Bus4	20.000	1	106.0	0.0	6.800	4.214	1.735	1.075				
Bus5	11.000	1	100.0	0.0								
Bus6	20.000	1	100.0	0.0	10.880	6.743	2.720	1.686				
Bus7	20.000	1	100.0	0.0	10.200	6.321	2.602	1.612				
Bus8	20.000	1	100.0	0.0	21.760	13.486	5.550	3.440				
Bus9	55.000	1	100.0	0.0								
Total Number of Buses: 9					56.440	34.978	14.359	8.899	0.000	0.000	0.000	0.000

Ge	Generation Bus						Generation	Mvar Limits		
ID	kV	Туре	Sub-sys	% Mag.	Angle	MW	Mvar	% PF	Max	Min
Busl	11.300	Swing	1	100.0	0.0					
Bus5	11.000	Voltage Control	1	100.0	0.0	25.000			30.000	0.000
Bus9	55.000	Voltage Control	1	100.0	0.0	20.000			40.000	0.000
						45.000	0.000			
						45.000	0.000			

ETAP 4 Project: Page: 19.0.1C Location: Date: 06-25-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: grid2 Config.: Normal

Line/Cable/Busway Input Data

ohms or siemens/1000 ft per Conductor (Cable) or per Phase (Line/Busway)

Line/Cable/Busway	_		Length	ı					
ID	Library	Size	Adj. (ft)	% Tol.	#/Phase	T (°C)	R	X	Y
Cable2-6	25MCUS1	750	8000.0	0.0	12	75	0.024798	0.093000	
Cable4-7	15MALS1	750	8000.0	0.0	12	75	0.036570	0.049700	
Cable_7-8	25MCUS1	750	8000.0	0.0	12	75	0.024798	0.093000	
Line2-3		203.	5280.0	0.0	1	75	0.130873	0.166755	0.0000010
Line_3-4		203.	5280.0	0.0	1	75	0.130873	0.166755	0.0000010
Line6-8		203.	5280.0	0.0	1	75	0.130873	0.166755	0.0000010

Line / Cable / Busway resistances are listed at the specified temperatures.

Project: ETAP Page: 5 19.0.1C Location: Date: 06-25-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Config.: Filename: grid2 Normal

2-Winding Transformer Input Data

Transformer				Rating				Z Variation	1	% Tap	Setting	Adjusted	Phase	Shift
ID	Phase	MVA	Prim. kV	Sec. kV	% Z1	X1/R1	+ 5%	- 5%	% Tol.	Prim.	Sec.	% Z	Туре	Angle
TR_1	3-Phase	100.000	11.300	20.000	6.50	34.10	0	0	0	0	0	6.5000	YNd	0.000
TR_2	3-Phase	100.000	20.000	11.000	6.50	34.10	0	0	0	0	0	6.5000	Dyn	0.000
TR_3	3-Phase	100.000	20.000	55.000	8.00	34.10	0	0	0	0	0	8.0000	YNd	0.000

Location: 19.0.1C Date: 06-25-2025

SN:

Contract:

Engineer: Study Case: LF Revision: Base

Filename: grid2 Config.: Normal

Branch Connections

CKT/	Branch	Col	nnected Bus ID	% Impe	% Impedance, Pos. Seq., 100 MVA Base					
ID	Type	From Bus	To Bus	R	X	Z	Y			
TR_1	2W XFMR	Bus1	Bus2	0.19	6.50	6.50				
TR_2	2W XFMR	Bus4	Bus5	0.19	6.50	6.50				
TR_3	2W XFMR	Bus8	Bus9	0.23	8.00	8.00				
Cable2-6	Cable	Bus2	Bus6	0.41	1.55	1.60				
Cable4-7	Cable	Bus4	Bus7	0.61	0.83	1.03				
Cable_7-8	Cable	Bus7	Bus8	0.41	1.55	1.60				
Line2-3	Line	Bus2	Bus3	17.28	22.01	27.98	0.0020147			
Line_3-4	Line	Bus3	Bus4	17.28	22.01	27.98	0.0020147			
Line6-8	Line	Bus8	Bus6	17.28	22.01	27.98	0.0020147			

Location: 19.0.1C Date: 06-25-2025

SN:

Contract:

Engineer:
Study Case: LF

Filename: grid2

Revision: Base
Config.: Normal

LOAD FLOW REPORT

	Bus		Volt	age	Gener	ation	Lo	ad			Load Flow				XFMR
	ID	kV	% Mag.	Ang.	MW	Mvar	MW	Mvar	II)	MW	Mvar	Amp	%PF	%Тар
* Bus1		11.300	100.000	0.0	25.652	9.579	0.000	0.000	Bus2		25.652	9.579	1399.0	93.7	
Bus2		20.000	99.342	-1.0	0.000	0.000	0.000	0.000	Bus6		18.614	7.193	579.9	93.3	
									Bus3		7.023	1.899	211.4	96.5	
									Bus1		-25.637	-9.092	790.4	94.2	
Bus3		20.000	97.708	-1.7	0.000	0.000	8.473	5.251	Bus2		-6.931	-1.783	211.4	96.8	
									Bus4		-1.542	-3.468	112.1	40.6	
Bus4		20.000	98.762	-1.8	0.000	0.000	8.492	5.263	Bus7		14.922	9.127	511.3	85.3	
									Bus3		1.568	3.500	112.1	40.9	
									Bus5		-24.982	-17.889	898.1	81.3	
* Bus5		11.000	100.000	-0.9	25.000	18.518	0.000	0.000	Bus4		25.000	18.518	1632.9	80.4	
Bus6		20.000	99.153	-1.1	0.000	0.000	13.554	8.400	Bus2		-18.597	-7.130	579.9	93.4	
									Bus8		5.043	-1.270	151.4	-97.0	
Bus7		20.000	98.593	-1.9	0.000	0.000	12.729	7.889	Bus4		-14.903	-9.101	511.3	85.3	
									Bus8		2.173	1.212	72.9	87.3	
Bus8		20.000	98.565	-1.9	0.000	0.000	27.152	16.828	Bus7		-2.173	-1.211	72.9	87.4	
									Bus6		-4.996	1.328	151.4	-96.6	
									Bus9		-19.983	-16.945	767.4	76.3	
* Bus9		55.000	100.000	-1.0	20.000	17.510	0.000	0.000	Bus8		20.000	17.510	279.0	75.2	

^{*} Indicates a voltage regulated bus (voltage controlled or swing type machine connected to it)

[#] Indicates a bus with a load mismatch of more than 0.1 MVA

19.0.1C Location: Date: 06-25-2025

Contract:

Engineer: Revision: Base Study Case: LF

Filename: Config.: grid2 Normal

Bus Loading Summary Report

Directly Connected Load Total Bus Load

SN:

Bus			Constar	nt kVA	Consta	ant Z	Cons	stant I	Ge	neric				Percent
ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar	MVA	% PF	Amp	Loading
Bus1	11.300										27.382	93.7	1399.0	
Bus2	20.000										27.202	94.2	790.4	
Bus3	20.000		6.800	4.214	1.673	1.037					9.968	85.0	294.5	
Bus4	20.000		6.800	4.214	1.692	1.049					30.726	81.3	898.1	
Bus5	11.000										31.111	80.4	1632.9	
Bus6	20.000		10.880	6.743	2.674	1.657					20.406	91.1	594.1	
Bus7	20.000		10.200	6.321	2.529	1.567					17.462	85.3	511.3	
Bus8	20.000		21.760	13.486	5.392	3.342					32.663	83.1	956.6	
Bus9	55.000										26.582	75.2	279.0	

^{*} Indicates operating load of a bus exceeds the bus critical limit (100.0% of the Continuous Ampere rating). # Indicates operating load of a bus exceeds the bus marginal limit (95.0% of the Continuous Ampere rating).

Project: ETAP Page: 9 19.0.1C Location: Date: 06-25-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: grid2 Config.: Normal

Branch Loading Summary Report

CKT / Branc	Busway / Cable & Reactor			Transformer						
CK1 / Branci				etor —		Loading (input)	Loading (output)	
ID	Туре	Ampacity (Amp)	Loading Amp	%	Capability (MVA)	MVA	%	MVA	%	
Cable2-6	Cable	7697.38	579.88	7.53						
Cable4-7	Cable	6144.38	511.27	8.32						
Cable_7-8	Cable	7697.38	72.86	0.95						
TR_1	Transformer				100.000	27.382	27.4	27.202	27.2	
TR_2	Transformer				100.000	31.111	31.1	30.726	30.7	
TR_3	Transformer				100.000	26.582	26.6	26.200	26.2	

^{*} Indicates a branch with operating load exceeding the branch capability.

Project:		ETAP	Page:	10
Location:		19.0.1C	Date:	06-25-2025
Contract:			SN:	
Engineer:		Study Case: LF	Revision:	Base
Filename:	grid2	stady case. 21	Config.:	Normal

Branch Losses Summary Report

	From-To	Bus Flow	To-From	Bus Flow	Los	sses	% Bus V	Voltage	Vd % Drop
Branch ID	MW	Mvar	MW	Mvar	kW	kvar	From	То	in Vmag
Cable_7-8	2.173	1.212	-2.173	-1.211	0.3	1.0	98.6	98.6	0.03
Cable2-6	18.614	7.193	-18.597	-7.130	16.7	62.5	99.3	99.2	0.19
Cable4-7	14.922	9.127	-14.903	-9.101	19.1	26.0	98.8	98.6	0.17
Line_3-4	-1.542	-3.468	1.568	3.500	26.1	31.3	97.7	98.8	1.05
Line2-3	7.023	1.899	-6.931	-1.783	92.7	116.1	99.3	97.7	1.63
Line6-8	5.043	-1.270	-4.996	1.328	47.5	58.6	99.2	98.6	0.59
TR_1	25.652	9.579	-25.637	-9.092	14.3	487.1	100.0	99.3	0.66
TR_2	-24.982	-17.889	25.000	18.518	18.4	628.9	98.8	100.0	1.24
TR_3	-19.983	-16.945	20.000	17.510	16.6	565.0	98.6	100.0	1.43
					251.6	1976.5			

^{*} This Transmission Line includes Series Capacitor.

Location: 19.0.1C Date: 06-25-2025

SN:

Base

Engineer: Study Case: LF Revision:

Contract:

Filename:

grid2

Config.: Normal

Alert Summary Report

% Alert Settings

	Critical	Marginal
<u>Loading</u>		
Bus	100.0	95.0
Cable / Busway	100.0	95.0
Reactor	100.0	95.0
Line	100.0	95.0
Transformer	100.0	95.0
Panel	100.0	95.0
Protective Device	100.0	95.0
Generator	100.0	95.0
Inverter/Charger	100.0	95.0
Bus Voltage		
OverVoltage	105.0	102.0
UnderVoltage	95.0	98.0
Generator Excitation		
OverExcited (Q Max.)	100.0	95.0
UnderExcited (Q Min.)	100.0	

Marginal Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus3	Bus	Under Voltage	20.000	kV	19.542	97.7	3-Phase

Project: ETAP Page: 12 19.0.1C Location: Date: 06-25-2025 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: Config.: grid2 Normal

SUMMARY OF TOTAL GENERATION, LOADING & DEMAND

	MW	Mvar	MVA	% PF	
Source (Swing Buses):	25.652	9.579	27.382	93.68 Lagging	
Source (Non-Swing Buses):	45.000	36.028	57.646	78.06 Lagging	
Total Demand:	70.652	45.607	84.093	84.02 Lagging	
Total Motor Load:	56.440	34.978	66.400	85.00 Lagging	
Total Static Load:	13.960	8.652	16.424	85.00 Lagging	
Total Constant I Load:	0.000	0.000	0.000		
Total Generic Load:	0.000	0.000	0.000		
Apparent Losses:	0.252	1.977			
System Mismatch:	0.000	0.000			

Number of Iterations: 3